


<p>BUND A</p> <p>VOLUME OF TOPSOIL STRIPPED: 5620m³</p> <p>VOLUME OF FILL TO FORM BUND: 29540m³</p>

IN ADDITION TO THE HAZARDS/RISKS NORMALLY ASSOCIATED WITH THE TYPES OF WORK DETAILED ON THIS DRAWING, NOTE THE SIGNIFICANT RESIDUAL HAZARDS SHOWN ON THIS DRAWING.

FOR INFORMATION RELATING TO USE,
CLEANING AND MAINTENANCE SEE THE HEALTH
AND SAFETY FILE.


IT IS ASSUMED THAT ALL WORKS WILL BE CARRIED OUT BY A COMPETENT CONTRACTOR WORKING, WHERE APPROPRIATE, TO AN APPROVED METHOD STATEMENT.

HAZARDS:

	Requirement to excavate on the face of the existing canal embankment. Risk of breach.
	Requirement to place and compact fill against existing canal embankment. Risk of breach.

NOTES:

1. DO NOT SCALE FROM THIS DRAWING. USE FIGURED DIMENSIONS ONLY.
2. ALL DIMENSIONS ARE INDICATIVE AND ARE TO BE CONFIRMED ON SITE.
3. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS NOTED OTHERWISE. ALL LEVELS ARE IN METRES RELATIVE TO ORDNANCE DATUM.
4. THE PURPOSE OF THIS DRAWING IS TO DETAIL THE USE OF ARISING FROM THE EXCAVATION FOR VYRNNYV RESERVE TO CREATE LANDSCAPE BUNDS.
5. VYRNNYV RESERVE IS DESIGNED BY OTHERS AND IS NOT SHOWN ON THIS DRAWING. HOWEVER AT THE DATE OF ISSUE THE RESERVE DOES INTERACT WITH THE WORKS ON THIS DRAWING.
6. THE FOLLOWING UTILITY OWNERS WERE CONTACTED AND STATED THEY HAD NO ASSETS IN THE AREA:
 - 6.1. XXX
 - 6.2. XXX
7. THE FOLLOWING UTILITY OWNERS WERE CONTACTED AND DID NOT RESPOND:
 - 7.1. XXX
 - 7.2. XXX
8. THE CONTRACTOR SHALL CONFIRM THE PRESENCE AND DETAILS OF ALL EXISTING STRUCTURES, PIPELINES AND OTHER SERVICES PRIOR TO COMMENCEMENT OF THE WORKS.
9. TOPOGRAPHIC SURVEY INFORMATION TAKEN FROM SURVEY OPERATIONS DRAWING 231096/001 TO 231096/015 (OCTOBER 2023). ALL LEVELS SHALL BE CONFIRMED BY THE CONTRACTOR PRIOR TO COMMENCEMENT OF THE WORKS.
10. TO BE READ IN CONJUNCTION WITH THE FOLLOWING DOCUMENTS:
 - 10.1. DRAWINGS 10048826-ARC-EWE-R1-DR-CE-00301 TO 00307
 - 10.2. 10048826-ARC-EWE-R1-TC-CE-00301 DESIGNER'S RISK ASSESSMENT
11. HEDGEROW/TREELINE BETWEEN CANAL, TOWPATH AND EMBANKMENT AND ON THE UPPER 50% OF THE EMBANKMENT WILL BE LAYED FOLLOWING TRADITIONAL HEDGE LAYING METHODS TO A REGIONAL STYLE, ALONG WITH GAP PLANTING AND COPPING WHERE LAYING IS NOT POSSIBLE. VEGETATION ON LOWER 50% OF EMBANKMENT TO BE REMOVED AND ROOTS GRUBBED OUT.



P01	17/03/25	FOR REVIEW	JM	JL	AH	AH
Rev	Date	Description	Prod.	Chk.	Rev.	App.



Projec

Montgomery Canal Restoration

Vyrnwy Reserve

Site

Parsons Lane
Llanymynech SY22 6SV

Client

Canal & River Trust
National Waterways Museum
Ellesmere Port



Registered

30 Fenchur
Street
London
EC3M 4BY

Coordinating office: 14-516-1816

1st Floor, 12 Kings Street
Leeds,
LS1 2HL
Tel: +44 (0)113 284 53

www.arcadis.com

© Copyright reserved

Drawing

VYRNWY RESERVE BUNDS
AND A GENERAL ARRANGEMENT

Designed: E.Flynn	Signed E.F	Date 17/03/2025
Produced: S.Thambe	Signed S.T	Date 17/03/2025
Checked: J.Langbridge	Signed J.L	Date 17/03/2025
Reviewed: A.Holt	Signed A.H	Date 17/03/2025
Approved: A.Holt	Signed A.H	Date 17/03/2025

Design Stage: FOR REVIEW

Original Size:	A1	Grid:	C
----------------	----	-------	---

Status Code:	Scale:
S3	As el

Status Description:

FOR R

Security Classification:

Drawing Number:

10048826 - ARC

R1 - DR -

	Revit
--	-------

1

1

BUND A GENERAL ARRANGEMENT

1 : 500

© OS Crown copyright

Print Date: 2025-03-25 13:22:35

C:\Users\marshalj8376\DC\ACCDocs\Arcadis ACC EU\AGB-10048826-Montgomery Canal Restoration-Vymwy Reserve Bunds\Project Files\04-WIP\04_ARC_Civils\B_Models\10048826-ARC-EWE-R1-DR-CE-00303.d